Annex B – Photographic Scope of Works

Room 001

Replace bulbs and diffuser

Air conditioner to remain

Ceiling tiles to be replaced

Store Room

Room 003

Close and fill data socket

Repair Door

Room 005

Remove and replace pan

Remove floor tiles and replace

Room 004

Pan and urinal can be saved

Room 006

Window is to be removed and new window installed and tied into the building fabric.

Windows to be removed and bottom blocked up to make building more symmetrical

Windows to look the same

Room 008

Install more suitable lights and fittings

Replace ceiling tiles

Tidy and redecorate

Remove and replace floor tiles

Windows to be reduced in size
New frame and bars installed
Hole blocked up and structurally secure

Removal of condensate line
Bathroom suite to be fully removed and replaced.
Removal of sharp edges and retiling of entire room

Additional railings installed
Post to be repaired and reset into the concrete.

Room 015/016/017/018

Replacement of light fittings
Installation of ceiling fans

Inspection of toilet and repair / replace if necessary

Room 013/014

Inspect roof leaking

Install ceiling fan

Install AC Unit

Replace ceiling tiles

Relocate weapons cabinet downstairs

Repair cupboard doors

Shutter Scope of Works

Window that needs shutter